

Now This Agreement Witnesseth as Follows: -

1. in this Agreement, words and expression Shall have the same meanings as are respectively assigned to them in the conditions of contract hereinafter referred to and they shall be deemed to from and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the Employer to the contractor as hereinafter mentioned, the contractor hereby covenants with the employer to execute and complete the works and remedy any defects therein in conformity in all aspects with the provision of the contract.
3. The Employer hereby covenants to pay the contractor in consideration of the Execution and completion of the work and the remedying the defects wherein contract price or such other sum as may become payable under the provisions of the contract at the times and in the manner prescribed by the contract.
4. The following documents shall be deemed to form and be ready and construed as part of this Agreement Viz.

- (i) Letter of Acceptance
- (ii) Notice to proceed with the works
- (iii) Contractor's Bid
- (iv) Condition of Contract: General and special
- (v) Contract Data
- (vi) Additional Condition
- (vii) Drawings
- (viii) Bill of Quantities and
- (ix) Any other documents listed in the contract Data as forming part of the contract.

In witnessed whereof the parties there to have caused this Agreement to be executed the day and year first before written.

The common Seal of _____ was

hereunto affixed in the presence of:

Witness 1. Arif Iqbal

Witness 2. Shahid Iqbal

Signed, Sealed and delivered by the said the employer and the contractor in the presence of

Witness 1. _____

Witness 2. _____

Biding signature of employer

Biding signature of contractor

ABRISHEK KUMAR
Abhishek
Proprietor

ABRISHEK KUMAR
Abhishek
Proprietor

sd
EXECUTIVE ENGINEER
P.H..DIVISON
NAWADA

P.H. DIVISION, NAWADA

ISSUE OF NOTICE TO PROCEED WITH THE WORK

Letter No. 1929

Date:- 04/11/2024

To,

Shri Abhishek Kumar
Village- Murhi,
Post-Darigoan Dist- Rohtas

Sub:- Name of The Work: Design, Construction, Supply, Testing, commissioning of Water Supply Schemes with Electric Driven Pumps for Non-Quality Wards of NAWADA District of Bihar on turn-key basis with 6 months Trial Run after Commissioning and Comprehensive Operation and Maintenance of 60 months after successful completion of Trial Run Period under Mukhyamantri Nishchay Non-Quality Affected Yojna Under P.H. Division, NAWADA BLOCK- Pakribarawan, Under P.H Sub-Division- Warisaliganj, Block- Pakaribarawan, Panchayat- Pakaribarawan South, Habitation- Chhoti talab, Ward No. 7, Habitation- Bartara, Ward No.12 Habitation- Mohanbigha, Ward No.12, , Habitation- Kartara, Ward No.13, Habitation- Jilwariya Ward No.13, Panchayat- Dumrawa, Habitation- Meghipur, Ward No. 1, (NITNO-08/PHEDNAWADA/2024-25 (MBNQ) GR-04) Under P.H. Division Nawada.

Ref:- Executive Engineer Letter of Acceptance No.1784 dated- 14.10.2024

Dear Sir,

Pursuant to your furnishing the requisite security as stipulated in ITB clause 31.1 and signing of the contract for Design, Construction, Supply, Testing, commissioning of Water Supply Schemes with Electric Driven Pumps for Non-Quality Wards of NAWADA District of Bihar on turn-key basis with 6 months Trial Run after Commissioning and Comprehensive Operation and Maintenance of 60 months after successful completion of Trial Run Period under Mukhyamantri Nishchay Non-Quality Affected Yojna Under P.H. Division, NAWADA BLOCK- Pakribarawan, Under P.H Sub-Division- Warisaliganj, Block- Pakaribarawan, Panchayat- Pakaribarawan South, Habitation- Chhoti talab, Ward No. 7, Habitation- Bartara, Ward No.12 Habitation- Mohanbigha, Ward No.12, , Habitation- Kartara, Ward No.13, Habitation- Jilwariya Ward No.13, Panchayat- Dumrawa, Habitation- Meghipur, Ward No. 1, (NITNO-08/PHEDNAWADA/2024-25 (MBNQ) GR-04) under P.H. Division, Nawada. The total cost of the work is **Rupees 13787300.00 (One Crore Thirty Seven Lakh Eighty Seven Thousand Three Hundred only)** You are hereby instructed to proceed with the execution of the said work in accordance with the contract document.

- (1) The total completion time for the work is 06 (six) calendar months from the date of issue of this letter.
- (2) No extra quantity of work will be done without prior permission of undersigned.
- (3) Important instructions must be entered in duly opened site order book.
- (4) Lowering of pipe in T/W will be done in presence of concerned J.E/A.E.
- (5) Treatment plant of CSIR or certified by CSIR or any other technology endorsed/approved by GOI, G.I/CPVC pipes, PVC Tank, I.S.I marked materials will be stored only after third party inspection with permission of undersigned and it will be used after satisfactory inspection at consignee end.
- (6) Monthly progress report will have to produce before undersigned.

4/11/24
Executive Engineer,
P.H.Division, Nawada

Memo No. 1929

Copy forwarded to Assistant Engineer, P.H. Sub Division, Warsaliganj for information. The work should be executed as per approved drawing and design.

4/11/24
Executive Engineer,
P.H.Division, Nawada

ABHISHEK KUMAR
Abhishek
Proprietor

ABHISHEK KUMAR
Abhishek
Proprietor

4/11/24
3/11/24

Memo No. 1929
Copy forwarded to S.E. P.H. Circle Gaya for kind information.

Dated:- 04/11/2024

Executive Engineer,
P.H.Division, Nawada

4/11/24
3 out 11/24
4/11

Memo No. 1929
Copy forwarded to C.E. P.H.E.D. Patna Zone Patna for kind information.

Dated:- 04/11/2024

Executive Engineer,
P.H.Division, Nawada

4/11/24
3 out 11/24
4/11

ABRISHEK KUMAR
Abhishek
Proprietor

ABRISHEK KUMAR
Abhishek
Proprietor

Memo No.: 1784.....Nawada/

Dated: 14.10.2024

LETTER OF ACCEPTANCE

From,

Executive Engineer
P.H.Division Nawada

To,

Shri Abhishek Kumar
Village- Murhi,
Post-Darigoan Dist- Rohtas

Sub:-

Name of The Work: Design, Construction, Supply, Testing, commissioning of Water Supply Schemes with Electric Driven Pumps for Non-Quality Wards of NAWADA District of Bihar on turn-key basis with 6 months Trial Run after Commissioning and Comprehensive Operation and Maintenance of 60 months after successful completion of Trial Run Period under Mukhyamantri Nishchay Non-Quality Affected Yojna Under P.H Division, NAWADA BLOCK- Pakribarawan, Under P.H Sub-Division- Warisaliganj Block- Pakaribarawan, Panchayat- Pakaribarawan South, Habitation- Chhoti talab, Ward No. 7, Habitation- Bartara, Ward No.12 Habitation- Mohanbigha, Ward No.12, Habitation- Kartara, Ward No.13, Habitation- Jilwariya Ward No.13, Panchayat- Dumrawa, Habitation- Meghipur, Ward No. 1, (NITNO-08/PHEDNAWADA/2024-25 (MBNQ) GR-04)

Ref:-

Divisional tender committee P.H.Division Nawada dated-14.10.2024

Sir,

This is to notify you that your Bid dated-03.09.2024 for execution the Design, Construction, Supply, Testing, commissioning of Water Supply Schemes with Electric Driven Pumps for Non-Quality Wards of NAWADA District of Bihar on turn-key basis with 6 months Trial Run after Commissioning and Comprehensive Operation and Maintenance of 60 months after successful completion of Trial Run Period under Mukhyamantri Nishchay Non-Quality Affected Yojna Under P.H. Division, NAWADA BLOCK- Pakribarawan, Under P.H Sub-Division- Warisaliganj, Block- Pakaribarawan, Panchayat- Pakaribarawan South, Habitation- Chhoti talab, Ward No. 7, Habitation- Bartara, Ward No.12 Habitation- Mohanbigha, Ward No.12, , Habitation- Kartara, Ward No.13, Habitation- Jilwariya Ward No.13, Panchayat- Dumrawa, Habitation- Meghipur, Ward No. 1, has been approved by Divisional Tender Committee in meeting held on dated-14.10.2024 for Rupees 13787300.00 only for the entire work. The approved rate is inclusive of all taxes and other charges. as Corrected and modified in accordance with the instructions to Bidders.

You are hereby requested to furnish performance security along with additional performance guarantee in shape as mentioned in the Bihar Financial Rules or Bank Guarantee duly pledged in favour of Executive Engineer P.H.Division Nawada detailed in para 31.1 of ITB for an amount equivalent to Rs.3854400.00 (PG=275800.00 & APG=3578600.00) only. within 15 days of the receipt of this letter of acceptance and sign the contract failing which action as stated in Para 31.1 of ITB will be taken.

ABHISHEK KUMAR
Proprietor

ABHISHEK KUMAR
Proprietor

Yours Faithfully

14/10/24
Executive Engineer
P.H. Division, Nawada

14/10

Memo No. 1784 Dated- 14/10/2024
Copy forwarded to Cashier, P.H.Division Nawada for information & necessary action.

14/10/2024
Executive Engineer
P.H. Division, Nawada
14/10

Memo No. 1784 Dated- 14/10/2024
Copy forwarded to Superintending Engineer P.H.E.D Gaya Circle Gaya for information & necessary action.

14/10/24
Executive Engineer
P.H. Division, Nawada
14/10
14/10/24

ABHISHEK KUMAR
Proprietor

ABHISHEK KUMAR
Proprietor

Financial Bid Sheet Group 04

Name of The Work: Design, Construction, Supply, Testing, commissioning of Water Supply Schemes with Electric Driven Pumps for Non-Quality Wards of NAWADA District of Bihar on turn-key basis with 6 months Trial Run after Commissioning and Comprehensive Operation and Maintenance of 60 months after successful completion of Trial Run Period under Mukhyamantri Nishchay Non-Quality Affected Yojna Under P.H. Division, NAWADA BLOCK- Pakribarawan, Under P.H Sub-Division- Warisaliganj

Date of Tender :-	03.09.2024
Estimated Cost:-	Rs.18,192,927.00
Earnest Money :-	Rs.363,900.00
Time of Completion :-	6 MONTHS
Cost of BSEDC Bid processing fee:-	Rs 5900.00 (to be paid online)
Cost of BOQ :-	Rs 10,000.00 (to be paid online)

Sl. No.	Particulars	Rate in Rs.	Qty.	Unit	Amount in Rs
1	ITEM WISE COST BREAKUP FOR				
	2	3	4	5	6
SECTION - A : EXECUTION PART					
1	Construction of 150mm X 90m deep Gravel packed T/W etc. all complete and as per direction of E/I. (In case of hilly areas depth may vary as per site condition, hydrology of the area and desired yield of the T-well) using U.P.V.C. Pipe & Strainer etc. all complete and as per direction of E/I.	Rs.375,000.00	6	Each	Rs.2,250,000.00
2	Constructing masonry Chamber 100x100x75 cm inside, in brick work in cement mortar 1:4 (1 cement : 4 coarse sand) for Tube Well, and RCC top slab 1:1.5:3 mix (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20mm nominal size) , necessary excavation, foundation concrete 1:2:4(1 cement : 2 fine sand : 4 graded stone aggregate 20 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3coarse sand) 12 mm thick with 5% cico finished with a floating coat of neat cement, out side plastering with cement mortar 1:4 (1 cement : 4coarse sand) 12 mm thick complete as per standard specifications & direction of E/I.	Rs.14,500.00	6	Each	Rs.87,000.00

ABHISHEK KUMAR,R/O-VILL-MURHI,POST-DARIGAON,PS-SASARAM,ROHTAS,BIHAR

Name and Address of the Bidder

ABHISHEK KUMAR
Proprietor

ABHISHEK KUMAR
Proprietor

Sd/-

EXECUTIVE ENGINEER
P.H.DIVISION
NAWADA

Sl. No.	Particulars	Rate in Rs.	Qty.	Unit	Amount in Rs
3	Supplying and installation, commissioning and testing of 3 HP Single phase Submersible pump and motor of KSB/Kirtoskar or equivalent make having discharge of 2.5 to 3.35 lps against a total head of 35 m including doing power and light wiring SUPPLYING & FITTING service wire extension of L T line (0.3Km) & 65 mm dia G.I medium class column pipe, 65mm dia Riser pipe (L), 65 mm dia N/R Valve, 65 mm dia flange and Supplying and installation of 7.5 KVA Stabilizer, taking single phase connection, Meter Board, Starter including power wiring all complete job etc all complete as per direction of E/I.	Rs.95,000.00	6	Each	Rs.570,000.00
4	Supplying all materials and Laying of distribution network including placing of 10000 litres PVC tank as per the directions of Engineer in Charge including Earthwork in 30m wide and 1.1m deep trenches, including crossing of ditches Road cutting and restoration and backfilling the trenches after laying of line, providing and laying HDPE pipe of 75 mm dia and 63 mm dia of (PE-PN10 rating) as per IS 4984/1995 and 50 mm and 40mm dia pipe (PE100-PN8 rating) as required including supplying all jointing materials etc. including all taxes, duties etc.-and incidental charges providing necessary thrust block where as required, construction of brick masonry chamber (60cm x 60cm x 75cm) for valves with cost of certification mark and fixing in trenches including the cost of fullway valves, earth work in back filling the trenches after laying of different types and sizes of pipe, fittings and valves with earth removed during excavation within initial lead and lift etc. including providing night guard, barrier and red light to safe guard against accident, testing of laid pipes etc. all complete job as per specification and direction of E/I.				
	G.I PIPE INCLUDING G.I FITTING				
	80 mm dia nominal bore from PVC tank to Distribution main	Rs.350.00	72	PM	Rs.25,200.00
	65 mm dia nominal bore used for washout and overflow from PVC Tank	Rs.315.00	24	PM	Rs.7,560.00
	50mm dia Pipe from T/well to PVC Tank	Rs.310.00	90	PM	Rs.27,900.00
	HDPE PIPE AND FITTING				
	90mm PE 100-PN10	Rs.475.00	580	PM	Rs.275,500.00
	75mm PE 100-PN10	Rs.425.00	880	PM	Rs.374,000.00
	63mm PE 100-PN10	Rs.275.00	1250	PM	Rs.343,750.00
	50mm PE 100-PN8	Rs.185.00	2580	PM	Rs.477,300.00
	40mm PE 100-PN8	Rs.175.00	3370	PM	Rs.589,750.00
5	Providing house connection for each house hold including supplying all materials, labours, tools and making ferrule connection with 20 mm dia MDPE and 15mm G.I Pipes with all fittings etc all complete.	Rs.2,250.00	755	Each	Rs.1,698,750.00

ABHISHEK KUMAR
Abhishek
 Proprietor

ABHISHEK KUMAR
Abhishek
 Proprietor

sd
EXECUTIVE ENGINEER
 P.H..DIVISON
 NAWADA

Sl. No.	Particulars	Rate in Rs.	Qty.	Unit	Amount in Rs
6A	Providing and erecting 8M high staging with ladder of ISA65x65x6 and 16mm dia MS bar as trade @ 400mm c/c and GI enclosure to house electric switch panel & treatment unit (where required) of suitably designed MS section of angle, channel, etc. as per drawing attached. Installation of Electronically Regulated Doser type chlorinator using Sodium Hypo Chlorite (Hypo NaOCl)	Rs.700,000.00	6	Each	Rs.4,200,000.00
7	Surveying and levelling using Total Station/DGPS or auto level instruments of the project area including transfer of relevant bench mark to establish the levels of strategic points at the selected position of the TWell, pumping station & attach the surveying data sheet with drawing of pipe line, map of location of HYDT & Steel structure etc. all complete work.	Rs.1,500.00	8.66	P/KM	Rs.12,990.00
	Sub Total-A				Rs.11,029,700.00
	SECTION - B : OPERATION AND MAINTENANCE PART (Should not be less than 25% of Sub Total of SECTION-A)				
9	Comprehensive Operation & Maintenance including repairs of Civil & Mechanical Structures, Supply of Spare parts, all Chemical, Energy Cost, Deployment of manpower, checking of status of supply in the command area, repairing of leakages, maintaining log book, data compilation, submission of daily / weekly / monthly and yearly report of both RAW and Treated water quality, getting endorsed / tested by state laboratories once in every month, replacing the filter media/damaged parts of any machinery / the machinery as a whole, annual / bi-annual maintenance of all built-up / installed structures / units under the scheme, including round-the-clock watch & ward to ensure potable water to the beneficiaries of the scheme for 60 calendar months from the date of completion of trial run. Electricity/power Bills will be borne by the agency based on the prevalent tariff excluding subsidies (if any) fixed by the Bihar electricity regulatory commission applicable for the "HGNJ" project. The contractor shall also ensure and facilitate to get the electricity connection in its name.	Rs.459,600.00	6	EACH	Rs.2,757,600.00
	Sub Total-B				Rs.2,757,600.00
	Total Cost of one Unit (A+B)				Rs.13,787,300.00

Bidders are required make the entries in the coloured cells only.

ABHISHEK KUMAR
Proprietor

ABHISHEK KUMAR
Proprietor

EXECUTIVE ENGINEER
P.H. DIVISION
NAWADA