

भारतीय गैर न्यायिक INDIA NON JUDICIAL

एक हजार रुपये  
रु.1000



ONE THOUSAND RUPEES  
Rs.1000

वर्षाक 24.10.24 अजीत कुमार सिंह वरुण किशुन सिंह लाकिन  
बिहार BIHAR मुरही रोहतास AGREEMENT FORM AV 848975  
कृष्ण प्रसाद स्टाम्प विक्रता  
पबरजिस्ट्री ऑफिस, गजगौर (मालदा)  
ला०न०-26 घन 1984-85

Agreement No: SBD- 02 /PHED NAWADA of 2024-25

Agreement value: Rs. 29301430.00

D.B Cost Rs.23441130.00, O&M Cost Rs.5860300.00

Time of completion: 06(Six) Calendar Months

Date of Work Order: Executive Engineer Letter No. 1927 dated-04.11.2024

Performance Security Amount Rs.820000.00

4/11/24 JUN 2024  
EXECUTIVE ENGINEER  
P.H. DIVISION  
NAWADA  
Treasurer Officer  
Nawada

Agreement

This agreement, made on 04.11.2024 between Executive Engineer P.H.Division, Nawada (hereinafter called " the employer" of the other part.) Ajit Kumar Singh S/o- Sri Kishun Singh At- Murhi, PO-Darigaon, Sasaram, Rohtas Dist- Sasaram (Bihar) Pin-821115 (here in after called "the contractor" of the other part).

Whereas the Employer is desirous that the Contractor execute Design, Construction, Supply, Testing, commissioning of Water Supply Schemes with Electric Driven Pumps for Non-Quality Wards of NAWADA District of Bihar on turn-key basis with 6 months Trial Run after Commissioning and Comprehensive Operation and Maintenance of 60 months after successful completion of Trial Run Period under Mukhyamantri Nishchay Non-Quality Affected Yojna Under P.H. Division, NAWADA BLOCK-Warisaliganj, Under P.H Sub-Division- Warisaliganj. Block- Warsaliganj, Panchayat- Barnawa, Habitation- Beldariya, Ward No.02, Panchayat- Dosut, Habitation- Dosut, Ward No.12, Panchayat- Kochgaon, Habitation- Jayant Nagar, Ward No.5A, Habitation- Naya Nagar, Ward No.5B, Habitation- Mahadalit tola, Ward No.12, Habitation- Dhanu tola, Ward No.6B, 8B, Panchayat- Kutri, Habitation Shivganj, Ward No.6, Panchayat- Makanpur, Habitation- Mahadalit tola, Ward No.7, Panchayat-Dosut, HabitationKathokari, Ward No.8, Panchayat- Mohiudinpur, Habitation- Mahadalit tola, Ward No.4, (NIT NO-07/PHED/Nawada/2024-25(SBNQ) Gr-06) Nawada of Bihar and employer has accepted the bid by the contractor for the execution and completion of such works and the remedying of any defects there in at a cost of Rupees 29301430.00 (Two Crore Ninty Three Lakh One Thousand Four Hundred Thirty only).

Ajit Kumar Singh  
4/11/24

4/11/24  
EXECUTIVE ENGINEER  
P.H. DIVISION



**OFFICE OF THE EXECUTIVE ENGINEER,**

**P.H. DIVISION, NAWADA**

**ISSUE OF NOTICE TO PROCEED WITH THE WORK**

Letter No. 1927

Date:- 04/11/2024

To,

**Ajit Kumar Singh**

**S/o- Sri Kishun Singh At- Murhi, PO-Darigaon, Sasaram, Rohtas**

**Dist- Sasaram (Bihar) Pin-821115 Email-ajitkumarsingh98010@gmail.com**

Sub:- Name of The Work Design, Construction, Supply, Testing, commissioning of Water Supply Schemes with Electric Driven Pumps for Non-Quality Wards of NAWADA District of Bihar on turn-key basis with 6 months Trial Run after Commissioning and Comprehensive Operation and Maintenance of 60 months after successful completion of Trial Run Period under Mukhyamantri Nishchay Non-Quality Affected Yojna Under P.H. Division, NAWADA BLOCK-Warisaliganj, Under P.H Sub-Division-Warisaliganj. Block- Warsaliganj, Panchayat- Barnawa, Habitation- Beldariya, Ward No.02, Panchayat- Dosut, Habitation- Dosut, Ward No.12, Panchayat- Kochgaon, Habitation- Jayant Nagar, Ward No.5A, Habitation- Naya Nagar, Ward No.5B, Habitation- Mahadalit tola, Ward No.12, Habitation- Dhanu tola, Ward No.6B, 8B, Panchayat- Kutri, Habitation Shivganj, Ward No.6, Panchayat- Makanpur, Habitation- Mahadalit tola, Ward No.7, Panchayat-Dosut, HabitationKathokari, Ward No.8, Panchayat- Mohiudinpur, Habitation- Mahadalit tola, Ward No.4, (NIT NO-07/PHED/Nawada/2024-25(SBNQ) Gr-06) Under P.H. Division Nawada.

**Ref:- Executive Engineer Letter of Acceptance No.1889 dated- 27.10.2024**

Dear Sir,

Pursuant to your furnishing the requisite security as stipulated in ITB clause 31.1 and signing of the contract for Design, Construction, Supply, Testing, commissioning of Water Supply Schemes with Electric Driven Pumps for Non-Quality Wards of NAWADA District of Bihar on turn-key basis with 6 months Trial Run after Commissioning and Comprehensive Operation and Maintenance of 60 months after successful completion of Trial Run Period under Mukhyamantri Nishchay Non-Quality Affected Yojna Under P.H. Division, NAWADA BLOCK-Warisaliganj, Under P.H Sub-Division-Warisaliganj. Block- Warsaliganj, Panchayat- Barnawa, Habitation- Beldariya, Ward No.02, Panchayat- Dosut, Habitation- Dosut, Ward No.12, Panchayat- Kochgaon, Habitation- Jayant Nagar, Ward No.5A, Habitation- Naya Nagar, Ward No.5B, Habitation- Mahadalit tola, Ward No.12, Habitation- Dhanu tola, Ward No.6B, 8B, Panchayat- Kutri, Habitation Shivganj, Ward No.6, Panchayat- Makanpur, Habitation- Mahadalit tola, Ward No.7, Panchayat-Dosut, HabitationKathokari, Ward No.8, Panchayat- Mohiudinpur, Habitation- Mahadalit tola, Ward No.4, (NIT NO-07/PHED/Nawada/2024-25(SBNQ) Gr-06) under P.H. Division, Nawada. The total cost of the work is **Rupees 29301430.00 (Two Crore Ninty Three Lakh One Thousand Four Hundred Thirty only)** You are hereby instructed to proceed with the execution of the said work in accordance with the contract document.

- (1) The total completion time for the work is 06 (six) calendar months from the date of issue of this letter.
- (2) No extra quantity of work will be done without prior permission of undersigned.
- (3) Important instructions must be entered in duly opened site order book.
- (4) Lowering of pipe in T/W will be done in presence of concerned J.E/A.E.
- (5) Treatment plant of CSIR or certified by CSIR or any other technology endorsed/approved by GOI, G.I/CPVC pipes, PVC Tank, I.S.I marked materials will be stored only after third party inspection with permission of undersigned and it will be used after satisfactory inspection at consignee end.
- (6) Monthly progress report will have to produce before undersigned.

Ajit Kumar Singh

Executive Engineer,  
P.H.Division, Nawada

04/11/24

4/11

Memo No. 1927 Dated:- 04/11/2024  
Copy forwarded to Assistant Engineer, P.H. Sub Division, Warsaliganj for information. The work should be executed as per approved drawing and design.

Executive Engineer,  
P.H.Division, Nawada 4/11/24

Dated:- 04/11/2024

Memo No. 1927  
Copy forwarded to S.E. P.H. Circle Gaya for kind information.

Executive Engineer,  
P.H.Division, Nawada 4/11/24

Dated:- 04/11/2024

Memo No. 1927  
Copy forwarded to C.E. P.H.E.D. Patna Zone Patna for kind information.

Executive Engineer,  
P.H.Division, Nawada 4/11/24

✓ AIT kr Rm

**Financial Bid Sheet Group 06**

**Name of The Work:** Design, Construction, Supply, Testing, commissioning of Water Supply Schemes with Electric Driven Pumps for Non-Quality Wards of NAWADA District of Bihar on turn-key basis with 6 months Trial Run after Commissioning and Comprehensive Operation and Maintenance of 60 months after successful completion of Trial Run Period under Mukhyamantri Nishchay Non-Quality Affected Yojna Under P.H. Division, NAWADA BLOCK-Warisaliganj, Under P.H. Sub-Division-Warisaliganj.

Date of Tender :- 03.09.2024

Estimated Cost:- Rs.30,216,038.00

Earnest Money :- Rs.604,400.00

Time of Completion :- 6 MONTHS

Cost of BSEDC Bid processing fee:- Rs 5900.00 (to be paid online)

Cost of BOQ :- Rs 10,000.00 (to be paid online)

**AJIT KUMAR SINGH, VILL.- MURHI,P.O.-DARIGAON,PS- SASARAM,ROHTAS,BIHAR**

**Name and Address of the Bidder**

Sl. No.

Particulars

ITEM WISE COST BREAKUP FOR

1

2

SECTION - A : EXECUTION PART

Construction of 150mm X 90m deep Gravel packed TW etc. all complete and as per direction of E/I. (In case of hilly areas depth may vary as per site condition, hydrology of the area and desired yield of the T-well) using U.P.V.C. Pipe & Strainer etc. all complete and as per direction of E/I.

1

Constructing masonry Chamber 100x100x75 cm inside, in brick work in cement mortar 1:4 (1 cement : 4 coarse sand) for Tube Well, and RCC top slab 1:1.5:3 mix (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20mm nominal size) , necessary excavation, foundation concrete 1:2:4(1 cement : 2 fine sand : 4 graded stone aggregate 20 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3coarse sand) 12 mm thick with 5% cico finished with a floating coat of neat cement, out side plastering with cement mortar 1:4 (1 cement : 4coarse sand) 12 mm thick complete as per standard specifications & direction of E/I.

2

Rate in Rs.

Qty.

Unit

Amount in Rs

3

4

5

6

Rs.327,000.00

10

Each

Rs.3,270,000.00

Rs.15,000.00

10

Each

Rs.150,000.00

*Ajit K. S.*

*Sof*

**EXECUTIVE ENGINEER  
P.H. DIVISION  
NAWADA**

Sl. No.	Particulars	Rate in Rs.	Qty.	Unit	Amount in Rs
3	Supplying and installation, commissioning and testing of 3 HP Single phase Submersible pump and motor of KSB/Kirloskar or equivalent make having discharge of 2.5 to 3.35 lps against a total head of 35 m including doing power and light wiring SUPPLYING & FITTING service wire extension of L T line (0.3Km) & 65 mm dia G I medium class column pipe, 65mm dia Riser pipe (L), 65 mm dia N/R Valve, 65 mm dia flange and Supplying and installation of 7.5 KVA Stabilizer, taking single phase connection, Meter Board, Starter including power wiring all complete job etc all complete as per direction of E/I.	Rs.124,000.00	10	Each	Rs.1,240,000.00
4	Supplying all materials and Laying of distribution network including placing of 10000 litres PVC tank as per the directions of Engineer in Charge including Earthwork in 30m wide and 1.1m deep trenches, including crossing of ditches Road cutting and restoration and backfilling the trenches after laying of line, providing and laying HDPE pipe of 75 mm dia and 63 mm dia of (PE-PN10 rating) as per IS 4984/1995 and 50 mm and 40mm dia pipe (PE100-PN8 rating) as required including supplying all jointing materials etc. including all taxes, duties etc.-and incidental charges providing necessary thrust block where as required, construction of brick masonry chamber (60cm x 60cm x 75cm) for valves with cost of certification mark and fixing in trenches including the cost of fullway valves, earth work in back filling the trenches after laying of different types and sizes of pipe, fittings and valves with earth removed during excavation within initial lead and lift etc. including providing night guard, barrier and red light to safe guard against accident. testing of laid pipes etc. all complete job as per specification and direction of E/I.				
	G.I PIPE INCLUDING G.I FITTING				
	80 mm dia nominal bore from PVC tank to Distribution main	Rs.640.00	120	PM	Rs.76,800.00
	65 mm dia nominal bore used for washout and overflow from PVC Tank	Rs.610.00	40	PM	Rs.24,400.00
	50mm dia Pipe from Twell to PVC Tank	Rs.620.00	150	PM	Rs.93,000.00
	HDPE PIPE AND FITTING				
	90mm PE 100-PN10	Rs.750.00	800	PM	Rs.600,000.00
	75mm PE 100-PN10	Rs.730.00	1600	PM	Rs.1,168,000.00
	63mm PE 100-PN10	Rs.620.00	2180	PM	Rs.1,351,600.00
	50mm PE 100-PN8	Rs.345.00	4600	PM	Rs.1,587,000.00
	40mm PE 100-PN8	Rs.295.00	5730	PM	Rs.1,690,350.00
5	Providing house connection for each house hold including supplying all materials, labours, tools and making ferrule connection with 20 mm dia MDPE and 15mm G.I Pipes with all fittings etc all complete.	Rs.2,650.00	1185	Each	Rs.3,140,250.00

Ajit Kumar

20  
EXECUTIVE ENGINEER  
P.H. DIVISION  
NAWADA

Sl. No.	Particulars	Rate in Rs.	Qty.	Unit	Amount in Rs
6	Providing and erecting 8M high staging with ladder of ISA65x5x6 and 16mm dia MS bar as trade @ 400mm c/c and GI enclosure to house electric switch panel & treatment unit (where required) of suitably designed MS section of angle, channel, etc. as per drawing attached. Installation of Electronically Regulated Doser type chlorinator using Sodium Hypo Chlorite (Hypo NaOCl)	Rs.875,000.00	10	Each	Rs.8,750,000.00
7	Surveying and levelling using Total Station/DGPS or auto level instruments of the project area including transfer of relevant bench mark to establish the levels of strategic points at the selected position of the TWWell, pumping station & attach the surveying data sheet with drawing of pipe line, map of location of HYDT & Steel structure etc. all complete work.	Rs.25,500.00	10	Each	Rs.255,000.00
8		Rs.3,000.00	14.91	P/KM	Rs.44,730.00
<b>Sub Total-A</b>					
<b>SECTION - B : OPERATION AND MAINTENANCE PART</b> (Should not be less than 25% of Sub Total of SECTION-A)					
9	Comprehensive Operation & Maintenance including repairs of Civil & Mechanical Structures, Supply of Spare parts, all Chemical, Energy Cost, Deployment of manpower, checking of status of supply in the command area, repairing of leakages, maintaining log book, data compilation, submission of daily / weekly / monthly and yearly report of both RAW and Treated water quality, getting endorsed / tested by state laboratories once in every month, replacing the filter media/damaged parts of any machinery / the machinery as a whole, annual / bi-annual maintenance of all built-up / installed structures / units under the scheme, including round-the clock watch & ward to ensure potable water to the beneficiaries of the scheme for 60 calendar months from the date of completion of trial run. Electricity/power Bills will be borne by the agency based on the prevalent tariff excluding subsidies (if any) fixed by the Bihar electricity regulatory commission applicable for the "HGNJ" project. The contractor shall also ensure and facilitate to get the electricity connection in its name.	Rs.586,030.00	10	EACH	Rs.5,860,300.00
<b>Sub Total-B</b>					
<b>Total Cost of one Unit (A+B)</b>					
					Rs.5,860,300.00
					Rs.29,301,430.00

Bidders are required make the entries in the coloured cells only.

AGIT 102. 03

Sef

**EXECUTIVE ENGINEER**  
**P.H..DIVISION**  
**NAWADA**