



First Party Name * : Not Applicable
 Second Party Name * : ANIL SINGH
 Purchased By * : ANIL SINGH
 Certificate Number : BR038156541736846790648
 Consideration Price : ₹0.00/-
 Stamp Duty Paid : ₹1000.00/-
 Registration Fee & Other Fees : ₹0.00/-
 LLR & Proc Fee : ₹0.00/-
 Miscellaneous Fees : ₹0.00/-
 Discure SC : ₹0.00/-
 Total Amount : ₹1000.00/- (One Thousand)



----- This stamp paper will only be valid if embossed below with special RED ink impression -----



Phone No:
 Sold To/Issued To:
 ANIL SINGH
 For Whom/ID Proof:
 ANIL SINGH

भारत INDIA
 INDIA NON JUDICIAL
 D S R OFFICE
 PATNA SADAR
 800001
 BIHAR
 बिहार
 भारतीय गैर न्यायिक



JAN-14-2025 14:57:12

₹ 0001000/-
 ZERO ZERO ZERO ONE ZERO ZERO ZERO

Other
 38156541736866632209-00109669
 3815654 82190

AGREEMENT FORM

**Agreement No – SBD- /MUNG/PHED/2024-25
 Agreement**

This agreement made the _____ day of 2024 between Executive Engineer, P.H. Division, Munger (here in after called, "The Employer") and Sri. Anil Singh, New Area Loha Singh Path, Sasaram, Dist- Rohtas (Bihar) (here in after Called, "The Contractor").

Whereas the Employer is desirous that the Design, Construction, Supply, Testing, commissioning of Water Supply Schemes with Electric Driven Pumps for Wards of Habitations/Ward- 2C,2D,2E,8A,8B of Panchayat- Bank, Ward- 09,11 of Panchayat- Ramnagar Under Block-Jamalpur, Dist- Munger. (Total no of Schemes- 07) on turn-key basis with 06 (six) months Trial Run after Commissioning and Comprehensive Operation and Maintenance of 60 (sixty) months after successful completion of Trial Run Period under Mukhyamantri Nishchaya (Non-Quality Affected) Yojna-II Under P.H. Division, Munger. (NIT-05/MUNG/PHED/2024-25, Group No. 03) (Here in after called "the Works") and the Employer has accepted the Bid by the Contractor for the execution and completion of such works and the remedying of any defects therein, at a Bid Price of Rs. 198.12010 Lakh (One Crore Ninety-eight Lakh Twelve Thousand Ten) only (Execution part Rs. 158.49590 Lakh and O&M part Rs. 39.62420 Lakh)

Anil Singh

**Executive Engineer
 P. H. Division, Munger**

NOW THIS AGREEMENT WITNESSETH as follows:

1. In this Agreement, words and expression shall have the same meanings as are respectively assigned to them in the conditions of contract here in after referred to and they shall be deemed to form and be read and construed as part of this Agreement.
2. In consideration of the payments to be made by the Employer to the Contractor as here in after mentioned, the Contractor hereby covenants with the Employer to execute and complete the works and remedy and defects there in conformity in all aspects with the provisions of the Contract.
3. The Employer hereby covenants to pay the Contractor in consideration of the Execution and completion of the Works and the remedying the defects where in contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.
4. The following documents shall be deemed to form and be ready and construed as part of this Agreement viz.
 - (i) Letter of Acceptance
 - (ii) Notice to proceed with the works
 - (iii) Contractor's Bid
 - (iv) Condition of Contract: General and Special
 - (v) Contract Data
 - (vi) Additional condition
 - (vii) Drawings
 - (viii) Bill of Quantities and any other documents listed in the Contract data as forming part of the Contract.

In Witnessed whereof the parties there to have caused this Agreement to be executed the day and year first before written.

The Common Seal of

_____ was hereunto affixed in the presence of:

Signed, Sealed and Delivered by the said


_____ in the presence of:

Binding Signature of Employer

Binding Signature of Contractor

Handwritten signature

Executive Engineer
P. H. Division, Munger



Clean Munger



Healthy Munger



Office of the Executive Engineer

Public Health Division, Munger

Phone No. 06344-226211, E-mail Id- ephed_mung@yahoo.in

LETTER OF ACCEPTANCE

Letter no- 1709 /Munger, Date 27/12/2024

To

Sri. Anil Singh,
New Area Loha Singh Path,
Sasaram, Dist- Rohtas (Bihar),
Mobile No. 8340309173
Email Id: - a8292anilsingh@gmail.com

Dear Sir,

This is to notify you that your Bid for NIT No – 05/MUNG/PHED/2024-25, Group No. 03 (Tender ID-78137) dated 25.10.2024 for Design, Construction, Supply, Testing, commissioning of Water-Supply Schemes with Electric-Driven-Pumps for Wards of Habitations/Ward- 2C,2D,2E,8A,8B of Panchayat- Bank, Ward-9,11 of Panchayat- Ramnagar Under Block-Jamalpur, Dist-Munger. (Total no of Schemes- 07) on turn-key basis with 6 months Trial Run after Commissioning and Comprehensive Operation and Maintenance of 60 months after successful completion of Trial Run Period under Mukhyamantri Nishchay (Non-Quality Affected) Yojna-II Under P.H. Division, Munger For Rs. 198.12010 Lakh (One Crore Ninety-eight Lakh Twelve Thousand Ten) only (Execution part Rs. 158.49590 Lakh and O&M part Rs. 39.62420 Lakh) is hereby accepted by the department.

You are hereby requested to furnish Performance Security (Including additional performance guarantee) in the form detailed in Caluse 31.1 of ITB for an amount equivalent to Rs. 6.71300 Lakh within 15 days of the receipt of this letter of acceptance valid up to 28 days from the date of expiry of defect liability period i.e up to 60 Months and sign the contract, failing which action as stated in Caluse 31.3 of ITB will be taken. All correspondence related to this tender will be sent to this Email Id: - a8292anilsingh@gmail.com . All undertaking uploaded in tender time on eproc2 website to be submitted in divisional office at the time of agreement.

Your Faithfully

[Handwritten Signature]
27/12/24

Executive Engineer,
P.H. Division, Munger

[Handwritten Signature]
27/12/24

[Handwritten Signature]

Executive Engineer
P. H. Division, Munger

NAME OF WORK - Design, Construction, Supply, Testing, commissioning of Water Supply Schemes with Electric Driven Pumps for Quality Wards of Munger District of Bihar on turn-key basis with 6 months Trial Run after Commissioning and Comprehensive Operation and Maintenance of 60 months after successful completion of Trial Run Period under Mukhyamantri Nishchay (Non Quality Affected) Yojna Under P.H. Division, Munger of Ward No. 2C,2D,2E,8A,8B of Panchayat-Bank, Ward-9,11 of Panchayat- Ramnagar Under Block-Jamalpur, Dist-Munger. (Total no of Schemes-07)

Date of Tender :-		25.10.2024			
Estimated Cost:-		Rs.20,650,800.00			
Earnest Money :-		Rs.414,000.00			
Time of Completion :-		6 MONTHS			
Cost of BSEDC Bid processing fee:-		As Applicable (to be paid online)			
Cost of BOQ :-		Rs 10,000.00 (to be paid online)			
Name and Address of the Bidder		ANIL SINGH ,VILL-MURHI,POST-DARIGAON,PS-SASARAM,ROHTAS, BIHAR			
Sl. No.	Particulars	Rate in Rs.	Qty.	Unit	Amount in Rs
ITEM WISE COST BREAKUP					
1	2	3	4	5	6
1	NAME OF WORK - Design, Construction, Supply, Testing, commissioning of Water Supply Schemes with Electric Driven Pumps for Quality Wards of Munger District of Bihar on turn-key basis with 6 months Trial Run after Commissioning and Comprehensive Operation and Maintenance of 60 months after successful completion of Trial Run Period under Mukhyamantri Nishchay (Non Quality Affected) Yojna Under P.H. Division, Munger of Ward No. 2C,2D,2E,8A,8B of Panchayat-Bank, Ward-9,11 of Panchayat- Ramnagar Under Block-Jamalpur, Dist-Munger. (Total no of Schemes-07)				
SECTION - A : EXECUTION PART					
1	Surveying and levelling using Total Station/DGPS or auto level instruments of the project area including transfer of relevant bench mark to establish the levels of strategic points at the selected position of the T/Well, pumping station & attach the surveying data sheet with design & drawing of distribution system by Loop/Water get or any other software etc., map of location of HYDT & Steel structure etc. all complete work.	2200.00	6.700	P/Km	Rs.14,740.00
2	Construction of 150mm x 125 m deep Gravel packed T/W etc. all complete and as per direction of E/I. (As per sub Estimate no.- 1)	445000.00	7	Each	Rs.3,115,000.00
3	CONSTRUCTION OF 200 MM x150 mm 125 MTR DEEP DRILLED HIGH YIELD TUBEWELL BY DTH RIG MACHINE WITH CASING M.S. PIPE (As per sub Estimate no.- 1A)		0	Each	Rs.0.00
4	Constructing masonry Chamber 100x100x75 cm inside, in brick work in cement mortar 1:4 (1 cement : 4 coarse sand) for Tube Well, and RCC top slab 1:1.5:3 mix (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20mm nominal size) , necessary excavation, foundation concrete 1:2:4(1 cement : 2 fine sand : 4 graded stone aggregate 20 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3coarse sand) 12 mm thick with 5% cico finished with a floating coat of neat cement, out side plastering with cement mortar 1:4 (1 cement : 4coarse sand) 12 mm thick complete as per standard specifications & direction of E/I.	15500.00	7	Each	Rs.108,500.00
5	Supplying all materials and Laying of distribution network as per the directions of Engineer in Charge including Earthwork in 0.3 m wide and 1.1m deep trenches. Including crossing of ditches Road cutting and restoration and backfilling the trenches after layig of line, providing and laying HDPE pipe of 75 mm dia and 63 mm dia of (PE-PN10 rating) as per IS 4984/1995 and 50 mm and 40mm dia pipe (PE100-PN8 rating) as required including supplying all jointing materials etc. including all taxes, duties etc.-and incidental charges providing necessary thrust block where as required, construction of brick masonry chamber (60cm x 60cm x 75cm) for valves with cost of certification mark and fixing in trenches including the cost of fullway valves, earth work in back filling the trenches after laying of different types and sizes of pipe, fittings and valves with earth removed during excavation within initial lead and lift etc. including providing night guard, barrier and red light to safe guard against accident, testing of laid pipes etc. all complete job as per specification and direction of E/I.				
	90mm PE 100-PN10	795.00	200	PM	Rs.159,000.00
	75mm PE 100-PN10	765.00	1550	PM	Rs.1,185,750.00

Anil Singh

Executive Engineer
P. H. Division, Munger

	63mm PE 100-PN10	685.00	1650	PM	Rs.1,130,250.00
	50mm PE 100-PN8	310.00	1400	PM	Rs.434,000.00
	40mm PE 100-PN8	295.00	1900	PM	Rs.560,500.00
6	Cost of Submersible Pump Set of KSB make having discharging 3.35 LPS at a total head of 35 M with suitable size of MSERW column pipe coupled with 3 H.P. submersible Motor 2900 RPM single phase and all necessary electrical and mechanical accessories etc. all complete set. (As per sub Estimate no.- 4)	167000.00	2	Each	Rs.334,000.00
7	Cost of Submersible Pump Set of KSB make having discharging 2.5 to 3 LPS at a total head of 35 M with suitable size of MSERW column pipe coupled with 2 H.P. submersible Motor single phase and all necessary electrical and mechanical accessories etc. all complete set. (As per sub Estimate no.- 4A)	155000.00	5	Each	Rs.775,000.00
8	supply, installation & commissioning of three phase 5 H.P submersible motor pump set with all accessories including extension of L.T. line from nearest source up-to pumping station.	2745.00	0	Each	Rs.0.00
9	Providing house connection for each house hold including supplying all materials, labours, tools and making ferrule connection with 20 mm dia MDPE (PE 80 grade PN 12.5) and 15mm CPVC Pipes with all fittings etc all complete.	2745.00	630	Each	Rs.1,729,350.00
10	Providing and erecting 8M high staging as per details attached with ladder of ISA65 x 65 x 6 and 16mm dia MS bar as trade @ 400mm c/c and GI enclosure to house electric switch panel & treatment unit (where required) of suitably designed MS section of angle, channel, etc. as per drawing attached.	875000.00	7	Each	Rs.6,125,000.00
			0	Each	Rs.0.00
11	CONSTRUCTION OF GSR 2.5M X 2.5M X 2M G.S.R		0	Each	Rs.0.00
12	CONSTRUCTION OF GSR 2.5M X 2M X 2M G.S.R		0	Each	Rs.0.00
13	Construction of 2.10x2.40mx2.4 m high of Switch room. (As per Sub Estimate-6A)		0	Each	Rs.0.00
14	Installation of Electronically Regulated Doser type chlorinator using Sodium Hypo Chlorite (Hypo NaOCl)	25500.00	7	Each	Rs.178,500.00
	Sub Total-A				Rs.15,849,590.00
	SECTION - B : OPERATION AND MAINTENANCE PART (Should not be less than 25 % of the Sub Total -A part)				
15	Comprehensive Operation & Maintenance including repairs of Civil / Mechanical Structures / including actual energy charges, Supply of Spare parts, all Chemical, Deployment of manpower, checking of status of supply in the command area, repairing of leakages, backwash, maintaining log book , data compilation, submission of daily / weekly / monthly and yearly report of both RAW and Treated water quality , getting endorsed / tested by state laboratories once in every month, replacing the filter media/damaged parts of any machinery / the machinery as a whole, annual / bi-annual maintenance of all built-up / installed structures / units under the scheme , including round-the clock watch & ward to ensure potable water to the beneficiaries of the scheme for 60 calendar months from the date of completion of trial run period.(6 months) The agency will get electricity connection in his name. Electricity / Power bills will be borne by agency based on the prevalent tariff excluding subsidies (if any) fixed by the Bihar Electricity regulatory commission (GOB). Applicable for the "HGNI" project payment will be done by department to the agency as per actual consumption of electricity bill, produced to the department by the agency. (Rate to be quoted per year)	Rs.113,212.00	7	per year	Rs.792,484.00
	Sub Total O&M Cost for 5 years (Sub Total-B)				Rs.3,962,420.00
	Total Cost of one Unit (A+B)				Rs.19,812,010.00

Bidders are required make the entries in the coloured cells only.

Executive Engineer
P.H. Division, Munger

18/18mm

Executive Engineer
P. H. Division, Munger

P.H. Division, Munger

Detailed Abstract of BOQ

Design, Construction, Supply, Testing, commissioning of Water Supply Schemes with Electric Driven Pumps for Quality Wards of Munger District of Bihar on turn-key basis with 6 months Trial Run after Commissioning and Comprehensive Operation and Maintenance of 60 months after successful completion of Trial Run Period under Mukhyamantri Nishchay (Non Quality Affected) Yojna Under P.H. Division, Munger.

(NIT-05/MUNG/PHED/2024-25 Gr-03)

Name of Work		Design, Construction, Supply, Testing, commissioning of Water Supply Schemes with Electric Driven Pumps for Quality Wards of Munger District of Bihar on turn-key basis with 6 months Trial Run after Commissioning and Comprehensive Operation and Maintenance of 60 months after successful completion of Trial Run Period under Mukhyamantri Nishchay (Non Quality Affected) Yojna Under P.H. Division, Munger.																	
Sl.No	Block	Panchayat	Village	Ward No.	CONSTRUCTION OF 150MM DIA X 125M DEEP TUBE WELL	DT BORING	Masonry Chamber	Rising & Distribution Pipe					Motor pump		House Connection	Staging	Switch room	Clorinator	
								90mm	75mm	63mm	50mm	40mm	3Hp	2Hp					
1		3	4	5	6	7	8	9	10	11	12	13	14	15	17	18	19	20	
1	Jamalpur	Bank	Mubarakchak	2C	1	0	1	0	250	250	0	300	0	1	80	1	0	1	
2	Jamalpur	Bank	Mubarakchak	2D	1	0	1	0	250	250	0	300	0	1	75	1	0	1	
3	Jamalpur	Bank	Mubarakchak	2E	1	0	1	0	200	200	200	300	0	1	75	1	0	1	
4	Jamalpur	Bank	Banaudha	8A	1	0	1	0	250	250	400	200	0	1	100	1	0	1	
5	Jamalpur	Bank	Banaudha	8B	1	0	1	0	250	250	400	200	0	1	100	1	0	1	
6	Jamalpur	Ramnagar	Ramnagar	9	1	0	1	100	100	200	200	300	1	0	100	1	0	1	
7	Jamalpur	Ramnagar	Chandarpura Mushahri	11	1	0	1	100	250	250	200	300	1	0	100	1	0	1	
				Total (A)	7	0	7	200	1550	1650	1400	1900	2	5	630	7	0	7	

Prasanna

**Executive Engineer
P.H. Division, Munger**

**Executive Engineer
P.H. Division Munger.**